



* All pipework must be balanced, that is, first in is last out (as shown).

* 1200 kPa Pressure relief valve required on the cold inlet of each unit.

* Isolating valves are recommended on the warm water outlet for each unit.